



Building Community®

Procurement Bid Office
Customer Center 1st Floor, Room 002
21 W. Church Street
Jacksonville, Florida 32202

03/18/2019

Addendum Number: **One (1)**

Title: **Brandy Branch T2 Addition**

JEA Solicitation Number: **055-19**

Response Due Date: **April 9, 2019**

Due Date Time: **12:00 PM**

Time of Opening: **2:00 PM**

This addendum is for the purpose of making the following additions, deletions and changes.

Add: A clarification meeting has been scheduled for Tuesday March 19, 2019, 3:00 PM. A teleconference line has been established: 1-888-714-6484, Participation Code: 817050. JEA will review the commercial requirements for the Bid and discuss any technical findings from the site walkthrough. Bidders may attend in person at the JEA Bid Office, 21 West Church Street, Jacksonville, FL 32202 or by Teleconference. Companies that attended the first Mandatory Prebid Meeting do NOT need to attend this second optional teleconference.

Change: Specific Instructions 1.2. – Change the address of the substation to 15701 West Beaver Street, Jacksonville, FL 32234.

Change: Specific Instructions 1.4. – Remove sections 1.4.1., 1.4.3, and 1.4.4. The Bidder should only include a construction schedule 1.4.2 and Schedule of Values 1.4.5.

Add: to Specific Instructions 2.4.6.C. – Bidder should also capture elevations for all new foundations as part of the as-built submittals.

Add: to Specific Instructions 4.2. – The Substantial Completion Date is 9/3/2019 and Substation Energization Date is 10/16/2019. These may be subject to change depending on when the NTP is issued to the winning bidder.

Delete: Specific Instructions 5.2.2. – Remove this section.

Clarification: Technical Specifications for Civil Structural and Architectural 4.2.8. – The Contractor shall provide and install a 2500 lb. mule tape upon completion of the final proof of the 230kV raceway by the cable installer.

The Contractor will not be responsible for installing the 230kV cable, providing the cable, or accessories. The cable vendor (Prysmian) will supply all cable, terminations, clamps, etc. as noted on the drawings. The Contractor will be responsible for installing the ductbank system, proofing said system, and installing 2500 lb. mule tape.

Supplier Inquiry 1: Does JEA have a tentative start date of the project.

JEA Response 1: 30 days after Bid Due Date.

Acknowledge receipt of this addendum on the Response Form