
# Pre-Bid Meeting for Drilling and Construction of Production Well No.s 1, 2, and Backup Well (No. 3) for Rivertown Water Treatment Plant (WTP) Project

## Rivertown WTP Project

• The Project is being implemented to provide and distribute additional potable water in JEA's service area in northwest St Johns County.

 The Rivertown WTP site and Well No. 1 Site are located at 7612 Longleaf Pine Parkway, St. Johns County, Florida.

• Well No. 2 and 3 sites are located east and north of the WTP site (see next slide).



## Rivertown WTP Project (continued)

- Owner: JEA
- Lead Engineering Consultant for the Project: CDM Smith
- Engineering Consultant for Wells: Jacobs
- Engineering Consultant for Pipeline: 4 Waters

## Rivertown WTP Project (continued)

- The Rivertown WTP Project will be constructed under 2 separate construction contracts:
  - Part 1, which is the work covered under this procurement action, consists of drilling, construction, and development of Production Wells 1 and 2 and Backup Well 3 and Associated Components as shown in the drawings and specifications.
  - Part 2, which will be covered by a future procurement action, will consist of the water treatment plant, well head assemblies, final site work for the well sites, and raw and finished water lines.

# Scope for Drilling and Construction of Production Wells 1 and 2 and Backup Well (No. 3) for the Rivertown WTP Project

- Production Wells 1 and 2 and associated components are included in the base bid.
- Well 3 (a backup well) and associated components are alternate bid items that are intended for construction dependent on costs and available funding.
- It is emphasized that award of alternate bid items (e.g., Backup Well (No. 3)) will be based on bid prices and available funding at JEA's discretion.

# Scope for Drilling and Construction of Production Wells 1 and 2 and Backup Well (No. 3) (continued)

The work includes, but is not limited to:

- Permitting, mobilization, and demobilization.
- Production Well 1:
  - preparing Well 1 site including clearing as needed;
  - installing temporary security fence;
  - installation sediment and erosion control measures;
  - overexcavating unsuitable materials;
  - providing and installing backfill;
  - drilling, constructing, developing, testing, logging/documenting the well, and disinfecting the well;
  - fluid management; and
  - restoration and stabilization.

# Scope for Drilling and Construction of Production Wells 1 and 2 and Backup Well (No. 3) (continued)

#### Production Well 2:

- preparing site and access road including clearing and grubbing;
- installation of temporary security fence;
- installation of sediment and control measures;
- overexcavating unsuitable materials;
- providing and installing fill;
- drilling, constructing, developing, testing, logging/documenting the well, and disinfecting the well;
- fluid management; and
- restoration and stabilization.

# Scope for Drilling and Construction of Production Wells 1 and 2 and Backup Well (No. 3) (continued)

#### Backup Well 3:

- preparing site and access road including clearing and grubbing;
- installation of temporary security fence;
- installation of sediment and control measures;
- providing and installing fill;
- constructing the access road including installation of raw water pipe, installation of sheet pile retaining wall, replacing curb and sidewalk;
- drilling, constructing, developing, testing, logging/documenting the well, and disinfecting the well;
- fluid management; and
- restoration and stabilization.

#### Schedule

- All work to be completed after the Notice to Proceed as follows:
  - Well No. 1:
    - Substantial Completion: 130 calendar days
    - Final Completion: 160 calendar days
  - Well No. 2:
    - Substantial Completion: 260 calendar days
    - Final Completion: 290 calendar days
  - <u>Backup Well No. 3</u> (if authorized):
    - Substantial Completion: 390 calendar days
    - Final Completion: 420 calendar days
- Substantial and Final Completion the wells interface with Part 2 Contract work.
- The Contractor shall prepare and submit a comprehensive project schedule at the beginning of the Project.

### **Technical Documents**

- Technical Specifications, Volume 1 of 2, Rivertown Water Treatment Plant Well No.s 1, 2, and Backup Well (No.3) Part 1 Production Well Drilling.
  - Geotechnical Exploration and Evaluation Report
  - Test Holes Report
  - Preliminary Wetlands and Listed Species Report
- Construction Drawings for JEA Rivertown Water Treatment Plant Well No.s
   1, 2, and Backup Well No. 3, Well No.s 2 & 3 Site Preparation for Well
   Drilling, Part 1, Volume 2 of 2 Drawings
- Permitting/Regulatory Status for (Part 1) Production Well Drilling Well No.s 1, 2, and Backup Well (No. 3) for the Rivertown Water Treatment Plant Project.
- An addendum may be issued to incorporate adjustments due to comments from SJR WMD on the Construction & Testing Plan for the Wells.

#### Points to Note

- Wells 1 and 2 and associated components are base bid. Backup Well (No. 3) and associated components are alternate bid items.
- Not all permits/regulatory approvals have been received. They are being worked. Field work will not be allowed on each well site until all permits/approvals have received for the respective well site. See the following document for current status:
  - Permitting/Regulatory Status for (Part 1) Production Well Drilling Well No.s 1, 2, and Backup Well (No. 3) for the Rivertown Water Treatment Plant Project
- Overexcavation of unsuitable soil and providing and installing fill.
- Provision and installation of granular backfill complying with the specifications to meet percolation requirements for ERP Stormwater Permitting.

## Points to Note (continued)

- The sites are near Bartram Trail High school:
  - Installation of temporary security fence is required before and during construction to minimize intrusion and potential safety concerns/injuries.
  - Must consider traffic
- Developer restrictions:
  - Imposed on Well 2 site.
  - Do Not clear/distribute beyond the limits of clearing!!
  - Do Not infringe on the Adjacent Properties!!
- Other interfaces:
  - Contractor for Part 2, which will be covered by a future procurement action, is for the water treatment plant, well head assemblies, final site work for the well sites, and raw and finished water lines.
  - Cellular companies for cell tower facility on east side of WTP site.
  - FP&L for power.

## Points to Note (continued)

- Protect adjacent properties
- Contractor must avoid track-out of mud, dirt, debris, etc onto Longleaf Pine Parkway. Contractor will be responsible for prompt removal and cleanup of any track-out that occurs.
- Contractor will need to provide temporary power and water supply.
  Options for water service include:
  - Install a temporary construction service off the finished water main in the Longleaf Pine Parkway ROW.
  - Install a temporary well for water supply during drilling operations only.
- Work area is within JEA property:
  - JEA access badges required
  - Masks are required if social distancing cannot be performed
  - No weapons, alcohol, illegal drugs

## Mandatory Site Tour

- Potential hazards:
  - Potential COVID 19 Exposure
  - Heat
  - Tripping hazards
  - Traffic on Longleaf Pine Parkway
  - Stinging insects, ticks, snakes, etc.
  - *Etc*
- PPE
  - Mask
  - Safety boots
  - Hard hats (optional)
  - Safety glasses
  - Reflective vest
- No weapons, alcohol, or illegal drugs