



Procurement Department Bid Office
Customer Center 1st Floor, Room 002
21 W. Church Street
Jacksonville, Florida 32202

June 19, 2019

ADDENDUM NUMBER: Four (4)

TITLE: Walnut Street Gravity Sewer Replacement

JEA IFB NUMBER: 096-19

BID DUE DATE: June 25, 2019

TIME OF RECEIPT: 12:00 Noon

TIME OF OPENING: 2:00 PM

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

JEA is providing the additional updated documents listed below:

- 096-19 Addendum 4 Appendix A - Additional Drawings
- 096-19 Addendum 4 Appendix B - Workbook

Clarification/Revision to answer given in Addendum 2

Question: JEA requires all pipe within a casing pipe to be restrained. Bell Restraints are typically used as restraints; but, they are also used to ensure pipe is not over-homed when it is being pushed through a casing pipe. Bell Restraints are typically used on pressure pipe. Our vendors have indicated that Bell Restraints are not made for the DR26 gravity sewer pipe. It has been suggested that DR25 pipe could be used in lieu of DR26 in the Casing. DR25 PVC pipe could be potentially used between MH 10 and MH 11 to avoid Transition Couplings. Please provide direction.

Revised Answer: Contractor shall install 36-inch gravity sewer PVC SDR 26 pipe between Manholes 10 & 11 as shown on the drawings. All pipe in the steel casing shall be restrained per JEA W/WW Standards.

CHANGES TO THE DRAWINGS

Sheet TTC-11: WORK ZONE 9

1. See attached sheet TTC-11 for modifications.

Sheet TTC-28: WORK ZONE 23 – MANHOLE REMOVAL

1. See attached sheet TTC-28 for modifications.

ATTACHMENTS

Replace Bid Drawings Sheet TTC-11 –WORK ZONE 9 and Sheet TTC-28 – WORK ZONE 23 – MANHOLE REMOVAL with the ones designated by Addendum 4

Replace the Bid Workbook with the one designated by Addendum 4