



Headquarters - Procurement Department
225 North Pearl Street
Jacksonville, Florida 32202

February 13, 2025

ADDENDUM NUMBER: Three (3)

TITLE: Construction Services for Cisco Drive to Garden Street 20-Inch Water Main Project

JEA SOLICITATION NUMBER: 1411906646

BID DUE DATE: ~~February 18, 2025~~ February 19, 2025

TIME OF RECEIPT: 12:00 PM

TIME OF OPENING: 02:00 PM

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

1. CHANGE – JEA is extending the bid due date:

Due to the President’s Day holiday, JEA will be moving the public bid opening meeting to February 19, 2025. Bids will be due that day at 12:00 PM ET.

2. CLARIFICATION – JEA is revising an answer to a previous question:

- **Question:** The north edge of Cisco Drive has multiple cracks in the asphalt, excavating 5’ to 7’ deep 6’ off the roadway will most likely create some settling and more cracking and the plans do not show any mill/ overlay of this area? Is this risk on the contractor or can JEA add an allowance for this operation?

Answer: The Contractor is responsible for protecting any existing asphalt that is not designated to be removed and replace on the plans. An allowance will not be added for this; **however, this item will be reviewed for payment on a case-by-case basis if protected, and additional settling/cracking occurs which requires repair.**

3. QUESTIONS - JEA is answering the following questions:

- **Question:** Can the JEA property located at 4770 Cisco Dr W be used as a laydown yard?

Answer: This will need to be further researched and coordinated internally. We can have an answer by the pre-construction meeting.

- **Question:** Will temporary asphalt be required for the installation of barrier wall for TTC Work Zone 8?

Answer: Yes, Temporary Pavement will be required for Work Zone 8 as indicated on the plans. TTC-11 shows the outline of the temporary asphalt which is in accordance with the FDOT Low Profile barrier wall detail 102-120 on TTC-19.

- **Question:** Sheet No. 6, Note 6 of the plans state that “residential access must be maintained at all times (typical for entire route)”. With the restoration of the concrete driveways requiring a minimum of 3 days cure time for vehicular traffic, is the contractor responsible for building alternative access drives?

Answer: Yes, the contractor is responsible for keeping access to all residences throughout construction which includes having a stabilized surface for temporary access until permanent access is restored.

- **Question:** It appears that new power poles were recently installed along Cisco Dr. Will the old power poles be removed prior to construction or are these to remain in place?

Answer: Yes, the poles will be removed prior to construction.