



Procurement Department Bid Section

August 13, 2025

ADDENDUM NUMBER: TWO (2)

TITLE: 1412013851 (IFB) JEA NGS – N35 (CT5) Non-Segregated Phase Bus Refurbishment FY26

PROPOSAL DUE DATE: September 3, 2025

TIME OF RECEIPT: 12:00 PM EST

**THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:**

1. **Question:** Would a proposal for replacement be considered instead of refurbishment?

**Answer:** JEA approves the use of new replacement bus components in lieu of refurbishment. New replacement components must meet or exceed the performance and design requirements of the existing system with a BIL rating of 125. All replacement components must comply with all applicable codes, standards, and regulatory requirements. Supporting documentation demonstrating compliance must be submitted for JEA review and pre-approval prior to bid due date.

2. **Clarification:** For the section below found in Section 1.2 of Technical Specifications, the responded shall provide all time and material rates associated with extra work as a separate attachment for the bid response. These rates will be used in the event of extra or unforeseen work.

Extra work – It is anticipated that repair work will be necessary. The contractor shall provide unit costs for each of the following items:

1. Clean electrical connections (6 inch by 3 inch X 6 – 108 square inches) with denatured alcohol. This is three phases in one location, both sides of the connection.
2. Silver plating of copper/aluminum connections (6 inch by 3 inch X 6 – 108 square inches)
3. Silver plating of copper/aluminum electrical connections. (6 inch by 4 inch X 6 – 144 square inches)
4. Replace damaged or missing 13.8kV connections – three half inch bolts, two Belleville's, two flats and nuts 1/2" (316 SS, not 304).
5. Replace cracked or damaged insulator – typical 15kV Meister.
6. Replace insulator hardware.

**ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE PROPOSAL FORM.**