



Procurement Department Bid Office
225 N. Pearl St.
Jacksonville, Florida 32202

September 29, 2025

ADDENDUM NUMBER: One (1)

TITLE: 1412050846 (IFB) Brandy Branch Generating Station Control Room Console Upgrade

RESPONSE DUE DATE: October 8, 2025

TIME OF RECEIPT: 12:00 PM

TIME OF OPENING: 2:00 PM

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

1. JEA adds “1412050846 Addendum 1”
2. JEA adds “1412050846 REVISED Appendix A - Technical Specifications”
3. JEA adds “1412050846 Mandatory Pre-bid Attendees

4. **Question:** Does the console need to be fixed or height adjustable?

Answer: Fixed Height

5. **Question:** Do you need computer storage underneath for CPU's, equipment, etc...

Answer: As for the storage underneath, we do not have CPUs to store as they are mounted in the BOP0 room and connect via KVM extenders. Depending on the setup for the E-Stops and the Yarway Drum Levels indicators will need a mounting point for terminal blocks (could be down with under floor junction box). Other than that, there are just 3 small form CPUs for Corp, nothing substantial.

6. **Question:** To insure ceiling mounts are correct height:
 - a. what is the dimension from floor to dropped ceiling?
 - b. what is the dimension from dropped ceiling to structure above?

Answer: a. Floor to the drop ceiling is 110.5” so 9’ 2.5”.
b. Drop ceiling to the building ceiling is 64” so 5’ 4”.

7. **Question:** Are the areas for operators be sit/stand or would it all be fixed height?

Answer: Fixed height

8. **Question:** Is any power or charging required on the worksurface? For example, 2 power outlets and 1 USB A+C charging port?

Answer: Yes, we would like the combo outlets consisting of 2 power outlets and 1 USB A+C charging port. The layout should include 2 on the left section, 2 on the center section, and 2 on the right section, for a total of 6.