



Procurement Department Bid Section
225 North Pearl Street
Jacksonville, Florida 32202

March 9, 2026

ADDENDUM NUMBER: Three (1)

TITLE: IFB 1412118646 CWSC Yard 2: Asphalt Demolition to Concrete Replacement

RESPONSE DUE DATE: ~~March 9, 2026~~, March 16, 2026

TIME OF RECEIPT: 12:00 PM EST

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

1. **Question:** Please Advise as to expected control and expansion joint spacing and whether joint cap and sealant will need to be applied to avoid water intrusion as joint material deteriorates.

Answer: Control Joints spaced every 15ft in both directions cut to depth 1.5 inches. Expansion joint required 200LF where the two slabs come together, and Joint sealant applied to prevent water intrusion

2. **Question:** Proceed with the use of expansion joint materials between the two sections.

Answer: Yes, Fiber Mesh (Polypropylene or steel) concrete shall be 4000psi.

3. **Question:** Please advise as to the saw cutting inside the fence line perimeter; the chain link fence posts appear to be set in concrete.

Answer: Saw cut inside perimeter 18" off fence line

4. **Question:** How far away from the posts should the saw cuts be made to avoid weakening the fence line while removal of asphalt and excavation take place?

Answer: Saw cut inside perimeter 18" off fence line

5. **Question:** Is there a water source available nearby onsite for use during the asphalt and concrete cutting operations?

Answer: There is a Fire Hydrant 200FT to the east of project. Will need a Hydrant Meter.

6. **Question:** Is there an area onsite that can be used for concrete truck/pump truck washout?

Answer: Truck Wash out must be done off site.

ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE RESPONSE FORM