



Procurement Department Bid Section
225 North Pearl Street
Jacksonville, Florida 32202

April 30, 2026

ADDENDUM NUMBER: One (1)

TITLE IFB 1412148247 JEA Pearl Street Service Center (PSSC) Yard Laydown

RESPONSE DUE DATE: ~~May 4, 2026~~ May, 18, 2026

TIME OF RECEIPT: 12:00 PM EST

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

1. JEA has changed the Response Due Date from ~~Monday May 4, 2026~~, to Monday May 18, 2026.

2. Question: Does the metal edging have to be furnished by the geocell manufacturer?

Answer: No, but it must meet the same technical requirement of the edging furnished by the geocell manufacturer. The new manufacturer must be sent to JEA for approval at least 5 days prior to response due date so it can be shared with all eligible bidders.

3. Question: Specs call for minimum 2" of fill over top of geocell. Is the intent to have a bare dirt lot and not see any of the gravel?

Answer: The fill over the top of the geocell is also granite. The intent is to have a minimum of 2" of rock over the geocell.

4. Question: Are all the utilities to this structure already shut off and disconnected?

Answer: Utilities are shut off and will be disconnected before contractor begins project.

5. Question: Confirming the fencing is excluded from our scope.

Answer: Permanent fencing is excluded. If the work sequence requires temporary fencing to maintain site security, the temporary fencing is the contractor's responsibility.

6. Question: Will we need to provide/install tree protection around it if it remains?

Answer: Tree protection will not be required.

ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE RESPONSE FORM