

Extra Work - Scope

Additional Materials, options for execution based on discovery during performance of the project:
Pricing includes installation of total quantity listed below.

#	Description	QTY	UOM	Unit Price	Total
1	Inspect additional connections.	5	EA		
2	Clean additional electrical connections.	5	EA		
3	Copper/Silver re-plating of aluminum connectors 16 Sq inches.	16	Sq in		
4	Silver re-plating of electrical connections	180	Sq in		
5	Replace damaged or missing 18 kV connection bolts (316 SS, not 304).	48	EA		
6	Replace cracked or damaged insulators - Delta Star B50 or equivalent.	3	EA		
7	Replace insulator hardware.	3	EA		
8	Replace hatch cover bolts and gasket	10	EA		
9	Welded Port for Access	1	EA		