



Procurement Department Bid Office  
Customer Center – 1<sup>st</sup> Floor, Room 002  
21 W. Church Street  
Jacksonville, Florida 32202

November 21, 2018

ADDENDUM NUMBER: Three (3)

---

TITLE: Deerwood Aquifer Recharge Pilot Test

---

JEA RFQ NUMBER: 95874

---

PROPOSAL DUE DATE: November 27, 2018

---

TIME OF RECEIPT: 12:00 PM

---

TIME OF OPENING: N/A

---

**THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR  
CLARIFICATIONS:**

- Page 4, Work by Contractor – Item 4: Changed to reflect flowmeter will be furnished and installed by Owner, not Contractor.
- Page 6, Monitor and Sampling Plan-Work by Contractor: Changed to reflect flowmeter will be furnished and installed by Owner, not Contractor.
- Attachment 1, Bill of Materials – Flowmeter: Changed to reflect the responsible party changes from Contractor to Owner, and meter type will be strap-on ultrasonic type.
- Attachment 2, Design Drawings No.'s 4 & 5 of 8: The Plan drawing will be revised after award if needed to reflect that a straight 20-foot length of 8" PVC pipe shall be installed between the two butterfly valves to allow the Owner-furnished flowmeter to be strapped-on, rather than 2 sections of flanged PVC pipe as shown. The pipe shall be installed continuous without a joint and slightly raised and supported on blocks to allow the meter straps to pass under the bottom of the pipe.

**Acknowledge receipt of this Addendum on the Proposal Form (Appendix B)**