



Procurement Bid Office
Customer Center 1st Floor, Room 002
21 W. Church Street
Jacksonville, Florida 32202

June 18, 2019

ADDENDUM NUMBER: One (1)

TITLE: SWITZERLAND CAP BANK INSTALLATION

JEA RFQ NUMBER: 97510

BID DUE DATE: June 21, 2019

TIME OF RECEIPT: 12:00 PM

TIME OF OPENING: 2:00 PM

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS in Red below:

Question 1: Is all of the material on site?

Answer 1: The control cable is not on site. There's a list in the bid document that explains what is on site and where it is located.

Question 2: Is the fence grounded?

Answer 2: Yes

Question 3: Will the contractor need to move the fence?

Answer 3: No

Question 4: All foundations seem to be installed, can you confirm?

Answer 4: All foundations are installed but please refer to the FDEP permit for storm water containment curb that needs installed

Question 5: Grounding appears to be installed. Is the below grade grounding installed as well?

Answer: 5: Yes

Question 6: Some of the steel columns are set, is all the steel on site?

Answer: 6: Yes

Question 7 : Are any of the conduits installed?

Answer:7: All conduits south of the substation perimeter are installed. Contractor is to extend all conduits from past the perimeter road to equipment as shown on drawings.

Question 8: Who is furnishing the PT junction box?

Answer 8: Contractor

Question 9: Is all material for the project on site?

Answer 9: Please see section IV of the technical specifications for material provided by owner and status of location.

Question 10: Is there a cable schedule available currently?

Answer 10: Please see revised technical specification to add cable schedule

Question 11: Do we furnish any conduit, fittings, or grounding material?

Answer 11: Contractor is responsible to provide any needed conduit and fittings. Any leftover conduit and fittings on site from previous contractor is available for use by new contractor. The bronze 5/8 grounding clamp is provided by JEA. All other needed grounding material is provided by contractor.

Question 12: Is the contractor to furnish and install any geo-web and rock? If so, what type of rock is required?

Answer 12: Please see Attachment A to these questions and answer for perimeter road repair. The road will need to be repaired the entire section in front of the new fence, approximately 150'. Repair will include removing any dirt/rock 6" below finished grade, compacting soil, installing Mirafi, Tensar, cellular confinement geogrid and rock. Please refer to drawings and civil specifications for final surfacing requirements in the substation expansion area.

Question 13: Is the fence grounded?

Answer 13: Yes.

14. Added - Additional drawing - Appendix A - Switzerland Cap Bank Installation Section 6 – Technical Specification (See Addendum 1 – attachment)

15. New additional - Appendix A - Switzerland Cap Bank Installation Section 7 - Technical Specification - Cable Schedule (See Addendum 1 – attachment)

16. New additional - Appendix A - Switzerland Cap Bank Installation Section 8 - FDEP Permit - Schedule (See Addendum 1 – attachment)

Acknowledge receipt of this addendum on the Bid Form