



Building Community®

Procurement Bid Office
Customer Center 1st Floor, Room 002
21 W. Church Street
Jacksonville, Florida 32202

July 16, 2019

ADDENDUM NUMBER: One (1)

TITLE: 128 Hedgerow Master Lift Station Fiber Build 2019

JEA ITN NUMBER: 97743

RESPONSE DUE DATE: July 24, 2019

TIME OF RECEIPT: 12:00 PM

TIME OF OPENING: 12:00 PM

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

Question:

1. Is tracer wire inside or outside of the conduit?

Answer:

1. Tracer wire is to be installed inside of the conduit.

Question:

2. Is JEA going to provide the communications rack, markers, and tags?

Answer:

2. JEA is providing a floor-mounted communications rack, as well as all markers, and all tags.

Question:

3. Per Sheet 12 on the Drawings, who provides 1" Inner duct SDR13-1/2? And what color should they be?

Answer:

3. All inner ducts should be provided by the contractor and should be gray in color.

Question:

4. Per Sheet 13 on the Drawings, please clarify the contractor responsibility.

Answer:

4. Contractor shall pull fiber and insert splice.

Question:

5. Per Sheet 15 on the Drawings, are all man-holes new?

Answer:

5. All man-holes are new.

Question:

6. What do contractors need to provide to St. Johns County?

Answer:

6. Contractors need to provide St. Johns County with As-Builts, and dates on the job-site.

Acknowledge receipt of this addendum on the Response Form