



**PROJECT DESIGN SEGMENT 20410
HAMILTON SUBSTATION BREAKER 307, 308, 310, 311, & 312 REPLACEMENTS
MATERIALS FURNISHED BY OWNER**

GENERAL NOTES:

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ORDERING THE JEA STOCK MATERIAL, INCLUDING THE 28.4KV VACUUM CIRCUIT BREAKERS, THROUGH THE JEA PROJECT REPRESENTATIVE AT LEAST TWO WEEKS IN ADVANCE OF NEED, RECEIVING AND LOADING THE MATERIAL AT AN ARBITRARY JEA LOCATION WITHIN DUVAL COUNTY, FLORIDA, TRANSPORTING THE MATERIAL TO THE SUBSTATION SITE, AND THEN OFFLOADING AND INSTALLING THE MATERIAL AT THE JOBSITE.
2. ALL MATERIALS PICKED UP OR RECEIVED BY THE CONTRACTOR SHALL REMAIN IN THE CARE, CUSTODY, AND CONTROL OF THE CONTRACTOR UNIL FINAL ACCEPTANCE. CONTRACTOR WILL BE RESPONSIBLE FOR ANY LOSS OR DAMAGE TO SAID MATERIAL.
3. THE CONTRACTOR IS RESPONSIBLE FOR FURNISHING AND INSTALLING MISCELLANEOUS ITEMS NOT LISTED IN THIS MATERIAL LIST, AS WELL AS ADDITIONAL MATERIALS LISTED ON THE DRAWINGS AND IN THE SPECIFICATIONS. THESE ITEMS MAY INCLUDE, BUT ARE NOT LIMITED TO CABLE TRENCH COMPONENTS, CONDUIT, CONDUIT FITTINGS AND HARDWARE, FASTENERS, CONTROL HOUSE ELECTRICAL EQUIPMENT, CABLE TRAY, WIREWAY, ELECTRICAL BOXES, ELECTRICAL POWER PANELS, TERMINAL BLOCKS, CONNECTORS, POWER CABLE, FITTINGS, ALL LABELING MATERIALS, ETC.

MATERIALS FURNISHED BY OWNER
HAMILTON SUBSTATION BREAKER 307, 308, 310, 311, & 312 REPLACEMENTS

PAGE.: 2 OF 2

QTY	DESCRIPTION	MANUFACTURER	COMMENTS	DELIVERED TO / PICKUP FROM	RESPONSIBILITY FOR TRANSPORT / OFF-LOAD
5	28.4 KV VACUUM CIRCUIT BREAKERS COMPLETE WITH 4 HOLE PADS	MEPPI STORE ROOM STOCK #VCBAR002		SEE NOTE 2	CONTRACTOR
1	2,500 FT. SHIELDED CONTROL CABLE, #10, FOUR CONDUCTOR	STORE ROOM STOCK # CAICN016		SEE NOTE 2	CONTRACTOR
1	2,375 FT. SHIELDED CONTROL CABLE, #10, TWENTY ONE CONDUCTOR	STORE ROOM STOCK # CAICN018		SEE NOTE 2	CONTRACTOR
1	125 FT. 1000 MCM, 61 STRAND, MEDIUM HARD DRAWN BARE COPPER	STORE ROOM STOCK # COBC0042		SEE NOTE 2	CONTRACTOR
30	CABLE TO FLAT 2 HOLE, BOLTED, STRAIGHT, TIN PLATED BRONZE	STORE ROOM STOCK # CNNTL730		SEE NOTE 2	CONTRACTOR
30	CABLE TO FLAT 4 HOLE BOLTED, STRAIGHT 4" 4/0-1000 MCM TIN PLATED BRONZE	STORE ROOM STOCK # CNNTL773		SEE NOTE 2	CONTRACTOR
10	TERMINAL, BOLTED,CABLE TO 2 HOLE PAD, TIN PLATED BRONZE WITH SILICON BRONZE HARDWARE	STORE ROOM STOCK #CNNTE046		SEE NOTE 2	CONTRACTOR
1	200 FT. 7#5 COPPERWELD	STORE ROOM STOCK # COBCW016		SEE NOTE 2	CONTRACTOR
LOT	BOLT KITS FOR CONNECTORS	STORE ROOM STOCK # BOLTE001		SEE NOTE 2	CONTRACTOR