



Building Community®

Procurement Bid Office
Customer Center 1st Floor, Room 002
21 W. Church Street
Jacksonville, Florida 32202

October 21, 2020

Addendum Number: **One (1)**

Title: **Dinsmore Forest Trail Solar Center - Manhole & Conduit System**

JEA Solicitation Number: **096-20**

Response Due Date: **November 10, 2020**

Due Date Time: **12:00 PM**

Time of Opening: **2:00 PM**

This addendum is for the purpose of making the following additions, deletions and changes.

Supplier Inquiry: Wanted to confirm that there is no overhead distribution work with this bid?

JEA Response: No OH work in the bid. However, 2 poles will have to be set at each end by others to turn the conduit up.

Supplier Inquiry: Please confirm that we are not responsible for pulling the cable in the conduit?

JEA Response: No cable pulling.

Supplier Inquiry: Are we responsible for clearing the trees on the road ROW to make room for the manhole installation, specifically stations 37 & 41.

JEA Response: Yes.

Supplier Inquiry: Are we responsible for reclaiming the land and driveways to their original conditions?

JEA Response: Yes.

Supplier Inquiry: Assuming we are to reclaim the ditches, can the ditches be bermed around the manholes or will the ditches have to stay in their current locations?

JEA Response: Ditches can be bermed.

Supplier Inquiry: Can you confirm that there are twenty (21) manholes to be priced? We counted twenty (22) on the drawings?

JEA Response: There are 22 manholes on order.

Supplier Inquiry: Can you provide the weights of the 12' x 6' x 7' manholes?

JEA Response: I believe the 12x6x7 MHs are 32,000#. Trevor?

Acknowledge receipt of this addendum on the Response Form