



Procurement Department Bid Section  
Customer Center 1<sup>st</sup> Floor, Room 002  
21 W. Church Street  
Jacksonville, Florida 32202

May 21, 2021

**ADDENDUM NUMBER:** One (1)

---

**TITLE:** IFB 1410326449 Cedar Bay Water Reclamation Facility Backup Power System

---

**BID DUE DATE:** June 15, 2021

---

**TIME OF RECEIPT:** 12:00 PM EST

---

**THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:**

1. **Question:** If we are on the EG1 Electrical Secondary Service Installations approved list of contractors; does that qualify us to bid the waste water project as a prime contractor, considering the majority of the work is Electrical?

**Answer:** No, The minimum qualifications remain the same. Only those companies approved to be on JEA's Responsible Bidders List (RBL) WP2 Water and Sewer Plant Systems Installation, Construction, Maintenance & Repair, as of the Bid Due Date can bid. The entity performing electrical work (whether Bidder or Subcontractor) must be on JEA's Responsible Bidders List (RBL) EG1 Electrical Secondary Service Installations as of the Bid Due Date.

2. **Question:** Is Hi Power considered a qualified supplier for this bid?

**Answer:** No, the generator manufacturer must be on the pre-qualified list. The approved vendors are Ring Power (Caterpillar), Zabatt Power Systems (AKSA), Cummins and Generac.

3. **Question:** Is JEA open to accepting an alternative manufacturer for the generator if it meets and/or exceeds the technical requirements?

**Answer:** No, the generator manufacturer must be on the pre-qualified list. The approved vendors are Ring Power (Caterpillar), Zabatt Power Systems (AKSA), Cummins and Generac.

4. **Clarification: The following Facilities Standards have been added to Appendix A – Technical Specifications section 26.32.13:**

1. Stairs / Platform are to be aluminum or Stainless Steel. One set of stairs on each side with a continuous platform under both doors. Powder coating is additional maintenance item when damaged will cause the steel to rust and corrode.
2. No Maintenance materials required as all of these Items are cover under the Maintenance Contracts in place. One exception is the required Touch-up Paint.
3. Add Generac as an approved vendor.
4. All JEA Fuels tanks required Ballistic rated UL 2085.
5. No Remote emergency E-Stop listed. Needs to be install 10 – 20 FT away from generator mounted on concrete post. Mushroom button in NEMA 4 enclosure. No Break Glass units permitted.
6. No RACOR water separator with bypass noted in specifications.
7. No Vapor Recovery Box noted in specifications.

8. Add note to refer to JEA Facilities Standards 26.32.13 for further clarifications and requirements.
9. All finned coolers need to be Bronzed Glow/dipped.

**ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID FORM**